The Integration of a Vision Based Inprocess Inspection System within the CassaMobile Project

Dr. Andrew Johnson, <u>Dr. Xiaoxiao Han</u>, Prof. Richard Bibb


24th January, 2017, MTC QCAM



Contents

- Introduction to CassaMobile project
- Introduction to the Additive Manufacturing (AM)
 Module
- The integration of the inspection system
- Conclusion


- €5.6 million, 11 partners
- http://www.cassamobile.eu/
- 36 months; September 2013 August 2016
- Keywords: Mobile, flexible, modular














The General Concept


Mobile, flexible, modular, small-footprint manufacturing system in a transportable container that can be easily configured for different products and processes

On-site manufacturing anywhere, enabling the benefits of localised service delivery without duplication of equipment at multiple locations





The Process Flow







The CassaMobile Container





Introduction to the AM module




CAD model



Basic specification

- Material Extrusion
- Dual Nozzles with water cooling
- Print speed: 600mm/min
- Minimal layer thickness:0.15mm
- Discrete control cabinets
- Integrated inspection camera and lighting

The Concept Overview




Hardware

- A high specification camera and lens
- Inspection lighting and power supply units
- An appropriate I/O box
- An industrial personal computer (IPC)

Specification

- Basler acA2040-90um camera
- Kowa LM12HC lens
- 300mm long ProPhotonix line light Qty 4
- National Instruments USB-6501 I/O box
- 24v power supply unit



Hardware components connections


Software

To facilitate the realisation of the proposed in-process inspection concept, a number of software requirements need to be satisfied, including:

- Generating reference image data
- Appropriately preparing/coding the I/O box
- Establishing the custom G-code to trigger the inspection system
- Designing and implementing an appropriate in-process software inspection system

UI (User Interface)


- Module one Displays images of the both the reference slice image as attained from the raw CAD data, and an image of the capture printed layer.
- Module two Enables the operator to set the number of required inspections, an acceptable calculated percentage difference between the reference and built images, and whether a perimeter or area inspection is to be performed.
- Module three Provides a clear indication to the operator as to the inspection status of the system
- Module four Allows the operator to commence or abort the inspection cycle.





Inspection system housing within the AM module











Inspection system initial testing









Future study

- Establishing a mean to automate the thresh-holding of captured images to optimise inspection performance.
- Determining an intelligent lighting protocol to minimise shadows within the inspection area of highly complex parts.
- Enhancing the storage and visibility of inspection results/data using
 3D graphic solutions.

Conclusion

- A vision based in process inspection system has been established
- It has been integrated in the AM module
- The system has been tested within the AM module in the container

CassaMobile Video

https://www.youtube.com/watch?v=PoyVWIaEHaA

Thank you for your attention. Any questions?

Dr Xiaoxiao Han x.han2@lboro.ac.uk

